

# International Connectivity Update 10 Sep 2013

T. R. ELASS
KAUST IT/Network & Communications



### **Early History**



- ➤ Graduate science & engineering university
- Constructed 2007-2009
- ➤ Students started Sep 2009
- ➤ Commodity Internet thru local ISP @ 200 Mbps
- ➤ Dedicated STM-64 (full lambda) to Amsterdam
  - Signaling bits used, carrier can't monitor
- ➤ Contract for 16 years, 99% availability, 1x10<sup>-12</sup> BER, terms on chronic outages

### 10G Link Reliability Statistics



- Can we receive highly reliable International connectivity through STC/Egypt?
  - $\square$ No (99% = 7.2 hours/month)
  - ☐ Why?
    - SLA breached in 19 of past 32 months, excluding force majeure cut 27Mar13-26Apr13
    - A backup link (2.5G) was activated on the 27<sup>th</sup> of March 2013
    - The availability of the 2.5G link for the month of April 2013 is 98.41%




### 10G & 2.5G LINK SLA & Reliability



The 10G link contractual SLA with STC is **99%** per month SLA was breached in 21 months over the past 31 months



Phase	Plan	Failover
Before 24.Jul.2013	<ul> <li>Amsterdam:         <ul> <li>No router installed</li> <li>Two International links (10G, 2.5G)</li> <li>One Internet link (1x 1Gbps @ Global Crossing)</li> <li>One link to Geant</li> <li>One link to Internet2</li> </ul> </li> </ul>	<ul> <li>No auto failover</li> <li>One Int'l link is used (2.5G)</li> </ul>



**International Connectivity Before 24.July.2013** 


#### **KAUST IT - Network & Communications**

Eng./Date: Hani AlHazmi Sheet No. Revision No. Location: Drawing Number: KAUST/Amsterdam ND20130408-001 001 001 08.Apr.13





Phase	Plan	Failover
	<ul> <li>Amsterdam (STC):</li> <li>No router installed</li> <li>Two International links (10G, 2.5G)</li> <li>Two Internet link (2x 1Gbps @ Level3)</li> <li>One link to Geant</li> </ul>	<ul> <li>Partial auto failover</li> <li>Internet only</li> <li>Failover within 30 seconds</li> </ul>
ı	<ul> <li>One link to Internet2</li> </ul>	<ul><li>Both Int'l links carry traffic</li><li>2.5G:</li><li>Géant</li></ul>
	<ul> <li>Live sine July 24<sup>th</sup>, 2013</li> <li>Coordination required among KAUST, NetherLight, SARA (Vancis) and Level3</li> </ul>	<ul> <li>Internet2</li> <li>Backup 1Gbps Internet</li> <li>10G:</li> <li>Primary 1Gbps Internet</li> </ul>



Phase I (Today)

Eng./Date: Location: Drawing Number: Hani AlHazmi KAUST/Amsterdam 08.Apr.13

ND20130408-001


Sheet No. Revision No. 002

001





Phase	Plan	Failover
II	<ul> <li>Amsterdam (STC):         <ul> <li>Install Cisco ASR 9K router</li> <li>Two International links (10G, 2.5G)</li> <li>Two Internet link (2x 1Gbps @ Level3)</li> <li>One link to Geant</li> <li>One link to Internet2</li> </ul> </li> <li>Go-live tentatively End of Sept 2013         <ul> <li>RFQ sent to Potential Supplier May 15, 2013</li> <li>RFQ Closed May 21, 2013</li> <li>Review of Technical Proposals May 25, 2013</li> </ul> </li> </ul>	<ul> <li>Full auto failover         <ul> <li>All services,</li> <li>Failover within 30 seconds</li> </ul> </li> <li>Both Int'l links will be used</li> <li>2.5G:         <ul> <li>Géant</li> </ul> </li> <li>Internet2</li> <li>Backup 1Gbps Internet</li> </ul> <li>10G:</li>
	<ul> <li>Review Commercial Proposals May 27, 2013</li> <li>Notice of Award Jun 1, 2013</li> <li>Delivery 6-8 weeks (some eqpt onsite, pending co-lo provisioning in Ams)</li> </ul>	<ul> <li>Primary 1Gbps Internet</li> </ul>



#### **International Connectivity** Phase II

#### **KAUST IT - Network & Communications**

Eng./Date: Hani AlHazmi Location: 08.Apr.13

KAUST/Amsterdam


Drawing Number: ND20130408-001 Sheet No. 001

Revision No. 001






Phase	Plan	Failover
III	<ul> <li>➤ Amsterdam (STC): <ul> <li>Install CRS router</li> <li>Two International links (10G, 2.5G)</li> <li>Two Internet links (2x 1Gbps @ Level3)</li> <li>One link to Geant</li> <li>One link to Internet2</li> <li>One link to GLIF (10G)</li> </ul> </li> </ul>	<ul> <li>Full auto failover</li> <li>All services,</li> <li>Sub-second failover</li> <li>Both Int'l links will be used</li> <li>2.5G:</li> <li>Geant &amp; Internet2</li> <li>Backup 1Gbps Internet</li> </ul>
	<ul> <li>Go-live tentatively Dec, 2013</li> <li>Aramco</li> <li>RFP released to potential bidders</li> <li>No estimated delivery time</li> </ul>	<ul> <li>10G:</li> <li>GLIF (upon request)</li> <li>Primary 1Gbps Internet</li> </ul>





Phase	Plan	Failover
IV	<ul> <li>➤ Amsterdam (STC):         <ul> <li>Two routers</li> <li>Two International links (10G, 2.5G)</li> <li>Two Internet links (2x 1Gbps @ Level3)</li> <li>One link to Geant/Internet2/GLIF</li> </ul> </li> <li>➤ Singapore/India (Mobily or ITC):         <ul> <li>One International link (622Mbps)</li> <li>One router</li> <li>One Internet link</li> </ul> </li> <li>➤ EPEG?</li> <li>➤ Long-term (2-3 years)</li> <li>➤ Link to East or EPEG not in 13-14 budget:         <ul> <li>RFI in May '13 for budgetary info</li> </ul> </li> </ul>	<ul> <li>➤ Full auto failover         <ul> <li>All services,</li> <li>Sub-second</li> </ul> </li> <li>➤ Both Int'l links will be used</li> <li>➤ 622M (STM-4):</li></ul>



### **Phase IV**

Eng./Date: Hani AlHazmi Location: Drawing Number: KAUST/Amsterdam ND20130408-001 08.Apr.13

Revision No. Sheet No. 001 001



### Network Upgrades...











# **Thank You**